CAUVERY RESERVOIR WORKS DIVISION.

FORM OF ADVERTISEMENT.

Notice is hereby given that sealed tenders will be received at the Office of the Superintending Engineer, Cauvery Reservoir Works Division, up to 30th June 1916, for supply of fuel of the kind noted in the specification. An approximate estimate of quantities is given below. These quantities are not guaranteed. The supply of fuel shall commence from 1st July 1916.

2. The conditions may be seen at the Superintending Engineer's Office, Cauvery Reservoir Works on all week days between the hours of 11 A.M. and 6 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Superintending Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Description of work.	Unit of work	Rate per unit

4. Each tender must be accompanied by a deposit of Rs. 500 in cash or Government Promisory notes, as earnest money, and be superscribed "tenders for supply of fuel for the North and South Banks Cauvery Reservoir Works," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer of Mysore who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor whose tender has been accepted, will be posted on the notice board in the Superintending Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money or rejected tenders will be returned.

9. From July 1916 to December 1916 the quantity to be supplied is 350 tons per month for the North Bank and 350 tons on the South Bank and from January 1917 to June 1917 at 200 tons per month for each Bank.

10. Tenders should be separately given for the South and North Banks.

Specification for fuel.

(1) The wood to be jungle fuel.

(2) The maximum and minimum which will be accepted are given below :—

Length.		*Thickness.*	
Maximum.	Minimum.	Maximum.	Minimum.
30″	18″	9″	4½″

(3) The billets are to be sawn and not chopped billets of over 7″ in diameter to be spilt.

(4) The wood to be stacked by the contractor in the portion approved of by the Superintending Engineer or his representative.

(5) Stocks must be rectangular in shape sides being vertical straight and the top level. The wood must be laid evenly straight and close the pieces compressing the walls must be laid at right angles to the direction of such walls, having first been sawn to an uniform length as above.

(6) The interior of the stacks must be packed as closely as possible, the pieces being regularly laid with their lengths all in one direction with no vacant space.

(7) The stacks to be built of such dimensions that a cubical contents of each in multiple of 75 cubic feet 1 s. ft. × 10 s. ft. × 5 ft. or 10 tons. (seventy-five cubic feet of closely packed wood will be accepted as equivalent to a ton).

(8) Superintending Engineer or his representatives will inspect the wood as it is being stacked and shall have power to reject any pieces that are hallow, rotten or otherwise unsuitable for fuel for boilers, he will also satisfy himself that the pieces are in accordance with the dimensions specified above and that the stacks are built as required. He shall have power to reject any stocks that do not in all respects comply with the terms of specification,

9. The wood in the stacking place must be at the risk of a contractor until it is stacked, measured and accepted by the Superintending Engineer or his representatives. The stacks will be measured thirty days after they are built allowing sufficient time for the fuel to dry.

10. When stacks are taken over the contractor or his representative must be present during the time of the measurement and must sign the record of measurement in token of his agreement to the correctness thereof.

11. Soft wood unsuitable for steaming purposes will not be accepted.

12. Jali, Thipyala, Devadari, Chigari, Hunsai, Heddarns, and other equal hard wood than those specified above which the contractor would like to supply may be supplied after he has got the previous sanction of the Superintending Engineer or his representatives. A cart-load of such fuel is to be brought in first when the same will be tested and if suitable the contractor will be given permission in writing, to such wood also in addition to the list of wood already approved of.

13. The quantity of fuel to be supplied from the date of the signing the bond up to June 1916 is tons per month.

14. Should the contractor fail to supply the stipulated quantity of fuel in two consecutive months the Superintending Engineer or his representatives can order for collection by separate agency at the risk of the contractor or cancel his contract crediting the whole or a part of the reserved amount to Government.

15. A reserve of 5 per cent will be withheld from the contractor's bill up to Rs. 2,500 and it will be paid till the accounts are finally settled.

16. The Superintending Engineer or his representatives is at liberty to cut and stack fuel by other agency from the trees in tank bed and other Government trees within the area of the Cauvery Reservoir works.

B. B. GARUDACHARYA,
For *Superintending Engineer, Cauvery Reservior Works.*

MYSORE CITY IMPROVEMENT TRUST BOARD.

Dated 5th May 1916.

Notice is hereby given that sealed tenders will be received at the office of the Chairman, City Improvement Trust Board, Mysore, up to 19th June 1916, for constructing open surface drains with cement concrete in the Chamundi extension. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1917.

2. The plans, detailed estimate and conditions may be seen at the Chairman's Office at the Town Hall, Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms, which may be obtained from the Chairman. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed :—

Statement of quantities for constructing open surface drains with cement concrete in Chamundi extension, Mysore.

No.	Items	Per	Quantity
	CONSTRUCTING CEMENT CONCRETE DRAINS.		
1	Earthwork excavation average soil	C. yd.	2,045
2	Cement concrete rendering the surface smooth with cement. (1 : 2½ : 5 field jelly).	C.ft.	26,190
3	Burnt stone covering slabs 5" to 6" thick dressed at sides and set in mortar ...	S. ft.	8,993
4	Burnt stone parapet 5" to 6" thick one line dressed and set in cement concrete including pointing.	,,	5,408

NOTE.—Cement will be supplied at a rate of Rs. 12 per barrel.

4. Each tender must be accompanied by a deposit of Rs. 250 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing open surface drains with cement concrete," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Government of Mysore, who do not bind themselves to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled, and his earnest money will be forfeited.